



A Better Place for All

Main Street
Creighton, 3263
P. O Box 62
Creighton 3263
Phone: +27 39 833 1038
Fax: +27 39 833 1179
Email: mailbox@ndz.gov.za
www.ndz.gov.za

**ADDENDUM FOR CONSTRUCTION OF HIMEVILLE CEMETERY GUARD HOUSE (COMM-
Q008/23/24)**

Date: 10/08/2023

Pricing schedule (MBD3)

This addendum serves to correct the pricing schedule error on page 9 (item no 3 and item no 14) of the document. Kindly receive the corrected pricing schedule.

RECOMMENDED BY:


MISS N. HOLIWE
SCM MANAGER

APPROVED BY:


MR/N.C. VEZI
MUNICIPAL MANAGER

I acknowledge receipt of this Addendum No.1

Name:.....

Signature:.....

Date:.....

Name of Tenderer (Company Name):.....

A Better Place for All



CONSTRUCTION OF HIMEVILLE CEMETERY GUARD HOUSE

MBD 3 - PRICING SCHEDULE

ITEM	DESCRIPTION	UNIT	QTY	RATE	TOTAL
1	Site establishment	Sum	1		
2	Clear site for all grub, shrubs, debris etc	Sum	1		
3	Construction of security house with brickwork inclusive of brickforce after every two courses of 3mx2.5m X 3m	m ²	15		
4	Supply and apply plaster on the internal walls with 15mm thickness	m ³	1.69		
5	Supply and apply plaster on the external walls with 15mm thickness	m ³	1.69		
6	Supply and install the concrete slab with 50mm thickness using 15MPa strength	m ³	0,5		
7	Supply and install well treated roof timber trusses with all necessary fittings	m ²	8		
8	Supply and install 0,58mm heavy duty chromadek IBR roof sheets	m ²	8		
9	Supply and install 0.5mm thickness glazing with 0.5x0.5m with Aluminium frames	No.	1		
10	Supply and install 0.5mm thickness glazing with 1.2x1.2m with Aluminium frames	No.	1		
11	Supply and apply quality PVA paint (Code EPL272) for the external walls	m ²	40		
12	Supply and apply quality PVA paint (Code EPL272) for the internal walls	m ²	40		
13	Supply and install rhino board ceiling with all fittings	m ²	7,5		
14	Supply and apply quality ceiling paint	m ²	7,5		

	Supply, install electrification and connect using 1.5mm diameter cables for lights and 2.5mm diameter cable for plugs. For tubing using plastic pipes. 1x ceiling light 1x outside light 2x wall socket plugs	sum	1		
15	Supply and install meranti single door with all fittings including 3 lever union keylock set	No.	1		
16	Provide Security	Mont hs	3		
17	Provision for CLO	Mont hs	3	4500	13500
	Sub Total				
	Contingencies @ 10%				
	Sub Total				
	Vat @ 15%				
	Total				

NB: This is a 3-month project, with a 1-month liability period. EPWP guidelines will be used for local labour and the wage rate is R 175/day or task.